



AREVA Experience in Dismantling of the Primary Circuit

ENKO 2014

Hans-Otto Rohwer
Project - Director
AREVA Back End Germany

11. ENKO, 23. – 24. April 2013 in Bratislava



Dismantling of Primary Circuit Components

Content



- ▶ Introduction of AREVA
- ▶ Optimized Primary Circuit Dismantling
- ▶ Competencies
- ▶ Project References
 - ◆ Boiling Water Reactor (Wuergassen RPV and Internals)
 - ◆ Pressurized Water Reactor (Stade RPV Internals)
- ▶ Summary

Our operating organization



Positioned as a leader in the back end of the cycle



Recycling

More than 75% of the global treatment market



D&D

Center of Competencies for D&D of NPP in Germany



Cleanup

Active at all nuclear sites in France



Logistics

No. 1 in nuclear transportation worldwide and No. 1 in SNF dry storage

Introduction

AREVA's Business Unit D&D

► BU current footprint



► Nuclear site reutilization projects worldwide

France, US (DOE), UK (Sellafield), Japan (Fukushima), Germany


► 1,400 employees, at 10 locations

► 400 MEUR revenue / year

► D&D Competence Center at AREVA Germany

- ◆ Assistance during post-closure phase / deregulation
- ◆ D&D engineering services and licensing support
- ◆ Project and site management
- ◆ Efficient decontamination (full-systems, components and equipment)
- ◆ Radiological characterization and nuclear measurement
- ◆ Disassembling, handling and packaging of highly activated components
- ◆ Spent fuel and radioactive waste management

Superphenix Reactor D&D



- ▶ Engineering and licensing support
- ▶ Procurement, erection, commissioning and operations
- ▶ Core unloading, fuel handling and storage
- ▶ Sodium draining, removal, neutralization, conditioning and storage
- ▶ Decontamination
- ▶ Large components removal, segmentation and packaging

Processes and Lessons Learned

- Plants of the fuel cycle-

Challenge

Marcoule: Dismantling of a military reprocessing plant

- Lifetime 40 years
- 1,000 plants to clean up
- 30,000 tons waste, where of 2% high level waste

Cadarache: Dismantling of a MOX fabrication plant

- Lifetime 2007 to 2013
- > 400 glove boxes, ca. 40 casks
- 600,000 working hours



La Hague: Dismantling of a civil reprocessing plant

- Dismantling and waste recycling combined
- 32,000 m3 waste to clean up
- 6,000,000 working hours

GB1: Dismantling of an enrichment plant


- ca. 150-200 kilo tons, α -contaminated
- D&D start 2015

La Hague




GB1

Cadarache




Marcoule



On-site management (operational safety, health physics, environment protection, Process organization...) as one of the essential challenges

Quantities of waste with the corresponding breakdown


► PWR Reactor
156.500 t
controlled area




Approx. 2% of the total waste of the controlled area has to be permanently disposed

AREVA Decommissioning Approach for an optimized D&D Concept

- From "Hot" to "Cold" → fastest possible reduction of the radiological inventory



Optimized Primary Circuit Dismantling Optimized Sequence




Conventional demolition



- From „Hot“ to „Cold“ → early removal of radiological inventory
- Installation mobile operating systems → faster clearing possible
- Awarding of overall work packages → Optimization of interfaces and usage of synergie effects

Optimized Primary Circuit Dismantling Hot to Cold

- ▶ *Dose rates on-site for subsequent lots reduced significantly*
- ▶ *Potential for radioactive release reduced significantly*
- ▶ *Early back fitting of mobile operating systems possible*
 - ◆ *Power supply with less stringent requirements*
 - ◆ *Aerosol monitoring / ventilation simplified significantly*
 - ◆ *Fire protection measures reduced and adapted to the dismantling activities*
 - ◆ *Waste water treatment simplified*
- ▶ *Supervisory procedure simplified*
- ▶ *Use of industry standards (instead of KTA-rules possible)*
- » *Nearly 100% of the radiological inventory removed early.
Significant simplification of further dismantling steps.*



Optimized Primary Circuit Dismantling Hot to Cold



Target: Fast reduction of the hazardous potential of the NPP – actually factor 100 Billion by 3 main measures.

**factor
10.000**



**factor
100.000**



**factor
100**



Plant shut down

Fuel unloaded

Full System Decont.
performed

Activated inventory
dismantled

~ 1 E21

~ 1 E17


~ 1 E12

~ 1 E10

Activity inventory of a NPP [Becquerel]

Phases of Decommissioning





Demonstration of the Complexity



**Savings of overall costs by
reduced time line & riskless phase out**

Competencies in Fuel Handling






- ▶ **As a lead manufacturer familiar with all requirements of a safe handling and storage**
 - ◆ Analysis of fuel rod integrity under given storage conditions
 - ◆ Studies and investigations about the fuel element characteristics under long term storage conditions
- ▶ **Design, manufacturing and operation of facilities for the storage and treatment of spent fuel elements**
 - ◆ Casks for transport and dry storage (TN24E)
 - ◆ Modular Dry Storage (NUHOMS)
 - ◆ Compact storage frame, Absorber Cartridge
 - ◆ Wet storage with passive cooling and protection against external effects
- ▶ **Service of fuel elements**
 - ◆ Fuel element inspection and repair
 - ◆ Encapsulation of defect fuel elements
- ▶ **Conditioning of used core internals**
 - ◆ Neutron source
 - ◆ Control rods, Instrumentation lance, Fuel element- components



Competencies Core Waste Processing in Spent Fuel Pool

► Cutting, Processing & Packing

- ◆ Control assembly
- ◆ Fuel element channel
- ◆ Control rod guide tube
- ◆ T-bolt
- ◆ Core instrumentation detector with yoke and shaft
- ◆ Drive rod
- ◆ Filter etc.



Competencies


Full System Decontamination

Benefits

- ▶ Reduction of personnel radiation exposure due to dose rate reduction
- ▶ Flexibility of D&D concept
- ▶ Facilitation of dismantling activities
- ▶ Reduction of overall radwaste volume during decommissioning

Recommendation to perform the FSD directly after shutdown

- ◆ All plant systems are fully operational
- ◆ Personnel with plant experience is on site
- ◆ Earlier benefits from dose reduction, leading to lower overall accumulated dose during Post operation and D&D




Note: All dose rates in mSv/h;
*dose rate estimated by KKS radiation protection

Competencies

Getting the Radiological Status

- ▶ Keyfactor for the Waste-Minimising:
 - ◆ Detailed knowledge about the radiological configuration of the components
- ▶ Combination of calculation and sampling
 - ◆ 3D-Activation-Calculation (specific activity and resulting dose rate)
 - ◆ Additional sampling for verification
- ▶ The aim is an as much as possible realistic judgement of the technical and radiological required measures
 - ◆ Avoidance of conservative considerations
 - ◆ Optimization of the waste packing and conditioning concept by minimizing the need of waste drums
 - ◆ Reducing the total dose rate (ALARA) of involved workers
 - ◆ More precise documentation for disposal application



Competencies Component Dismantling

- ▶ Studies, Concept development, Engineering, Licensing
- ▶ Dismantling & Replacement of Primary Circuit Components (NSSS)
 - ◆ Reactor Pressure Vessel (RPV)
 - ◆ Reactor Internals
 - ◆ Primary pipes, Pressurizer, Pumps, Steam Generator
 - ◆ Core Waste Processing (cutting & packing)
 - ◆ Equipment Design & Manufacturing (tools, machinery, water purification...)

» *Over 30 years experience in Replacement & Dismantling of Primary Circuit Components (NSSS)*



Competencies Cutting Techniques and Equipment

Cold cutting processes

- Water jet cutting
- Sawing
- Milling
- Shearing
- Nibbling
- Unscrewing
- Grinding
- Drilling
- Wire sawing (rope, diamond)


Thermal cutting processes

- Plasma cutting
- Torch cutting
- Powder flame cutting
- Laser cutting
- Oxygen lance
- Petrogen cutting (gasoline-oxygen)
- Electric discharge machining (EDM)
- Contact arc metal cutting (CAMC)



Specific Equipments

- Water Treatment System (mechanical filter / hydro cyclone)
- Cleaning Systems (high pressure water cleaning)
- Lifting devices, gripper, shears, press,



Competencies Waste Treatment Systems

- ▶ **Waste water and waste treatment systems**
 - ◆ Waste treatment concepts and studies
 - ◆ Supply of waste water and radwaste treatment systems
- ▶ **Design of waste water treatment systems**
 - ◆ Evaporation systems
 - ◆ Centrifugation systems
 - ◆ Filtration
- ▶ **Design of liquid waste treatment systems**
 - ◆ Drying systems
 - ◆ Cementation systems
 - ◆ Bituminization systems
- ▶ **Equipment for solid waste treatment**
 - ◆ Sorting boxes
 - ◆ In-drum compactors
 - ◆ Supercompactors
 - ◆ Balers
 - ◆ Shredders
 - ◆ Drying boxes



Drum Filling Station

Turn-key projects for:


- ▶ Hot Laundry
- ▶ Hot Workshops
- ▶ Decontamination Workshops
- ▶ HVAC systems

Project Reference


Core Waste Processing in Spent Fuel Pool

► Dismantling of Control Rods NPP Isar 1

Layout Spent fuel pool



Packing Plan of Mosaik casks





Sawing device



Spent fuel


Working area



Project Reference: Wuergassen NPP (BWR) Dismantling of RPV Internals and RPV




Würgassen NPP (BWR, 670 MWe)




Project Reference: Wuergassen NPP (BWR) Dismantling of RPV Internals




Jet Pumps & CRGT



Steam-Water-Separator with T-Bolts




Steam Dryer
(Scope NIS: wire sawing after concrete filling)




Project	Year
Contract for dismantling control rod guide tubes and jet pumps	11/2003
Successfully completed	12/2004
Contract for dismantling T-bolts of steam-water-separator	05/2004
Successfully completed	01/2005
Contract for dismantling the cyclones of steam-water-separator	10/2005
Successfully completed	11/2006
Contract for dismantling the remaining internals (core cover, upper core grid, lower core grid, core shroud, feed water sparger, jet pumps, etc)	04/2006
Successfully completed (TP91 phase 1 and 2)	11/2008
Contract for dismantling the reactor pressure vessel (cylindrical part)	02/2008
Successfully completed	02/2010

Project Reference: Wuergassen NPP (BWR) CRGT and Jet Pumps



- ▶ On-site activities:
09 – 12/2004
- ▶ Cut mass: 22 tons
- ▶ 110 CRGT
(L=410 cm, D=27 cm)
- ▶ 18 jet pumps
(L=320 cm, D=19 cm)





- ▶ Remote handled cutting under water in spent fuel pool
- ▶ Pulling-out and pre-cutting by band saw
- ▶ Final cutting by nibbling and packing into primary cask
- ▶ Drying of casks and inserting into 200l-drum

Project Reference: Wuergassen NPP (BWR)



T-Bolts

► 40 T-bolts


- ◆ Total mass: 8 tons
- ◆ Separating from steam-water-separator
- ◆ Cutting of T-bolts using a band saw
- ◆ Packing of cut parts into primary cask and after drying into 200l-drums



Project Reference: Wuergassen NPP (BWR) Steam-Water-Separator



- ▶ Order receipt: 10/2005
- ▶ Engineering & procurement: 7 months
- ▶ Cutting & packing: 7 months
- ▶ UW-cutting in set down pool
- ▶ Core cover was dismantled later on
- ▶ Cutting of web plates via shearing
- ▶ Separating of cyclones via compass saw
- ▶ Cutting of median support ring via pot saw
- ▶ Separating of stand pipes via compass saw
- ▶ Cut mass: 35 tons (120 cyclones)
- ▶ Compacting of cut parts using an UW-compactor, packing into 200l drums






Project Reference: Wuergassen NPP (BWR) Remaining Internals

► Phase 1: Mobile internals in set down pool


- ◆ Core cover (remaining from steam-water-separator)
- ◆ Upper core grid
- ◆ Lower core grid
- ◆ Core Instrumentation

→ Packing into primary casks & 200l drums



Project Reference: Wuergassen NPP (BWR)

Cutting Activities Phase 1




▶ Cutting of core cover


- ◆ **Water Abrasive Suspension Slicing - WASS**
(cutting speed ca. 50 mm/min)
- ◆ Compass saw
- ◆ Hydraulic shear



Mockup test at AREVA




Gripping a calotte segment after cutting



Cutting of core cover calotte

Project Reference: Wuergassen NPP (BWR)

Cutting Activities Phase 1



Project Reference: Wuergassen NPP (BWR) Remaining Internals

► Phase 2: Rigidly installed internals in RPV

- ◆ Core Shroud
- ◆ Components close to RPV-wall
e.g. sample magazines, standpipes of feed water
sparger and jet pumps

→ Packing into primary casks & 200l drums



Final cutting of standpipe



First cut on core shroud



Project Reference: Wuergassen NPP (BWR)

Cutting and Packing Strategy



Complex cutting due to various nozzles.
Adapted grippers with force and form lock.

Project Reference: Wuergassen NPP (BWR)


Dismantling of RPV

► RPV data

- ◆ Total weight of cylindrical part: 320 tons
- ◆ Height: 15 m
- ◆ Cut segments: 252 pcs.
- ◆ Packing for final storage (29 KC)

► Applied cutting techniques

- ◆ Water Abrasive Suspension Slicing
 - Water pressure: 2000 bar
 - Material thickness: 137 mm
 - Cutting speed: 20 mm/min
- ◆ Band saw (for RPV flange)
 - Cutting height: 1100 mm
 - Flange thickness: 425 mm



Requirement: in-situ cutting on air

Project Reference: Wuergassen NPP (BWR) Overview on installed Infrastructure



• Shielding plate




• Complex RPV crane
(handling tools and
dismantled pieces)



• Rail systems and cranes for
transportation (remote-operated)



• Rail system and cranes for
container loading and
conditioning (remote-operated)



► Installation of cranes and auxiliary
equipment

(e.g. steel structure) for transportation of
RPV segments and packing into
containers

Project Reference: Wuergassen NPP (BWR) Shielding Plate

- ▶ Total mass: 32 tons
- ▶ Attached to rotating crane above RPV
- ▶ Lowered down following the dismantling progress



Reduction of collective dose

Project Reference: Wuergassen NPP (BWR) Rotating Crane



2t lifting unit

1t lifting unit

35t lifting unit

5,5t lifting unit



Project Reference: Wuergassen NPP (BWR) Cutting Technique


► RPV flange

- ◆ Vertical cuts: band saw
 - Wall thickness: 450 mm
 - Avoidance of aerosols
- ◆ Horizontal cuts: WASS
 - Avoidance of aerosols
 - Wall thickness: 140 mm
 - No jamming



► RPV cylindrical part

- ◆ Vertical and horizontal cuts: WASS
 - Avoidance of aerosols
 - Limited clearance to insulation: 200 mm
 - No thermal impact to insulation



Project Reference: Wuergassen NPP (BWR) On-site Impressions



Vertical segmentation
of RPV flange



Positioning of RPV
segment for transport to
container loading station





Gripper removing RPV segment



Packing of RPV segment
into KONRAD container

Project Reference: Wuergassen NPP (BWR) Cutting and Packing Strategy



- ▶ Total mass: < 20t
- ▶ Difference in center of gravity: < 10%



**Correlation of cutting and packing plan
for reducing the number of containers.**

Project Reference: Wuergassen NPP (BWR) Packing and Conditioning

- ▶ Rail system for up to 5 Konrad containers (KC)
- ▶ Cranes for handling of cut pieces, KC and concreting device
- ▶ Weighing system for KC
- ▶ Shielding plates for KC
- ▶ Camera surveillance
- ▶ Covering station



AREVA NP

Project Reference: Wuergassen NPP (BWR) Water Purification

- ▶ Collecting the water-abrasive-kerf mixture
- ▶ Deposition of abrasive and kerf material using the principle of a hydro cyclone





» Deposition directly into 200l drums –
no additional handling necessary.

Project Reference: Wuergassen NPP (BWR) Schedule



	2008			2009			2010	
	Q2/08	Q3/08	Q4/08	Q1/09	Q2/09	Q3/09	Q4/09	Q1/10
Project duration	24 months							◇ April 2010
Engineering phase	12 months							
Installation of cutting equipment				6 months				
Dismantling of RPV				13 months				

Project Reference: Stade NPP (PWR) Dismantling of RPV Internals




► Dismantling conditioning and packing for final storage of RPV Internals (2007-2009)

- ◆ Remote controlled underwater segmentation and packing
- ◆ Total mass of 85 tons
- ◆ 158 shielded casks and 10 containers
 - Upper Core Internals
 - Lower Core Internals with Core Barrel
 - Core Support Structure


37 shielded casks were saved.

Project finished successfully in time.
Dose application limited as specified.
No accident at work.


Project Reference: Stade NPP (PWR) Pool Layout



Project Reference: Stade NPP (PWR) On-site Impressions



Project Reference: Stade NPP (PWR) On-site Impressions



Project Reference: Stade NPP (PWR) Schedule

	2008					2009		
	2007	Q1/08	Q2/08	Q3/08	Q4/08	Q1/09	Q2/09	Q3/09
Project duration	32 months							Aug. 2009
Engineering phase	21 months							
Installation of cutting equipment				7 months				
Dismantling in reactor pool				11 months				
Post treatment and cleaning of cutting area				13 months				

Würgassen (BWR) and Stade (PWR)

- ▶ Dismantling, conditioning and packing for final storage of RPV as well as RPV Internals


- ◆ Stade RPV Internals (2007-2009)

- Remote controlled underwater segmentation and packing
- Total mass of 85 tons
- 158 MOSAIK and 10 KONRAD containers
- 37 MOSAIK containers were saved due to optimization of packing strategy

- ◆ Würgassen RPV + Internals


- Dismantling and packing of Internals (2003-2009)
- Total mass of 160 tons
- Dismantling and packing of RPV (2008-2010)
- Total mass of 320 tons

» **10% to 20% of waste containers were saved - Projects were finished successfully in time - Collective dose limited as specified - No accident at work**



Optimized Primary Circuit Dismantling Summary

- ▶ ***D&D projects are driven by costs, to implement an optimization process from the very beginning is key***
 - ◆ *Optimized strategy and sequencing of the dismantling (hot to cold) will provide serious economical savings*
 - ◆ *Larger dismantling packages will reduce interfaces and ease the coordination efforts on site*
 - ◆ *Early usage of mobile systems will ease the large-scale release for dismantling*
- ▶ ***Social transition has to be addressed with priority and to be planned at an early phase in the D&D planning***
- ▶ ***Concept, Planning & Project Management will influence the success of the project much more than the used technique***



The AREVA Competence Centre for Dismantling provides a solid base for the successful execution of your decommissioning project.